OFFICE OF THE SPECIAL DUTY OFFICER, BIRTHDAY FESTIVITIES.

Tender Notice No. O. 2852, dated 3rd May 1933.

Notice is hereby given that sealed tenders will be received by 3 P.M. at the Office of the Special Duty Officer, Birthday Festivities, General and Revenue Secretariat, Bangalore, up to 15th May 1933 for constructing about half a dozen temporary latrines, about ten motor sheds and about 20 to 25 temporary sheds at Mysore to serve as kitchen and bath rooms for the use of Guests and Representative Assembly Members to be accommodated in several buildings. The specification of the sheds and latrines are given below. The work should be completed by the 28th May 1933.

2 Each tender must be accompanied by a deposit of Rs. 50 in cash or Government Promissory Notes as earnest money, and be superscribed "Tender for construction of temporary sheds at Mysore," in default of which, tenders will be rejected.

3. The final acceptance of any tender will rest with the Special Duty Officer, Birthday Festivities, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

4. Within three days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond with a security deposit of Rs. 100 in default of which his tender will be considered cancelled and his earnest money will be forfeited.

5. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Special Duty Office at the Indian Guests' Quarters, Mysore, in due course. No enquiries regarding the acceptance of a tender will receive any reply.

6. On acceptance of any one of the tenders, the earnest money on rejected tenders will be returned.

SPECIFICATIONS.

1. Each kitchen and bath shed to measure about 20' x 10' divided into three compartments made out of thatti mat walls and doors and thatched roof with grass on the top. Each shed to consist of one kitchen cistern and one bath cistern and one big oven and two small ovens. Ground to be cleaned and to be-washed with cowdung and the drainage around the shed arranged for.

2. Each motor shed to measure about 18' x 12' made out of thatti mat walls and doors and thatched roof with grass on the top. Ground to be cleared and scraped and the drainage around the shed arranged for.

3. Each latrine to measure about 4' x 5' built of thatti mat walls and provided with a pit 3' x 1' x 1'. The ground to be cleaned and scraped.

4. The materials to be used may be taken back by the contractor after the occasion and the grounds levelled and made clean and tidy after removal.

C. S. SRINIVASACHAR,
Special Duty Officer.

MYSORE RAILWAYS.

LOCO AND CARRIAGE DEPARTMENT.

Notification, dated 5th May 1933.

Sealed tenders are invited for handling coal at the following stations of the Mysore Railways for two years from 1st July 1933 to 30th June 1935 as per details furnished.

Stations.

Metre Gauge.

Mysore, Bangalore, Shimoga Town, Arsikere, Chikjajur and Birur.

Narrow Gauge.

Kolar and Bangalore.

Note.—At Bangalore Narrow Gauge the rate quoted for unloading and stacking should be inclusive of the charges for transhipment of coal from Metre Gauge to Narrow Gauge wagons.

Tram Gauge.

Tarikere.

Schedule of Work.

(*a*) Unloading coal from wagons and stacking on ground in the Loco Yard within a lead not exceeding 100 feet. The stacks should be of uniform size consisting of about 100 tons of coal.	Rate per ton to be quoted.
(*b*) Loading coal into wagons from Loco Yard within a lead not exceeding 100 feet.	
(*c*) Loading or unloading beyond the lead of 100 feet for every 100 feet.	